

MINNESOTA DEPARTMENT OF TRANSPORTATION  
OFFICE OF MATERIALS ENGINEERING

Federal Aid, State Funds, County and Municipal Federal Aid Projects

These schedules outline the sampling and testing required for most materials used in highway construction. Some items that are rarely used or materials of recent development are often covered by special provisions and may not be shown on the schedule. When sample sizes required for testing exceed 35 pounds, please submit multiple containers of the material with no individual container weighing more than 35 pounds.

Small quantities of materials may be accepted without sampling and testing. A small quantity is defined as any total quantity, for the whole project, of one material which is smaller than the minimum quantity required for testing unless modified by the individual material items. These materials shall be from known, reliable sources, perform satisfactorily and meet the requirements for purpose intended. The inspection report (Form 2415) should include a statement to this effect and show the source. Form 2403 may be used to report small quantities of diverse materials from different sources. Form 2415 and Form 2403 (or approved revisions) are referenced in the Schedule of Materials Control for project record documentation and are required to be maintained in the project file.

Where items of small quantity are used in a critical location or significantly influence the safety, performance, strength or durability of major construction items, prior approval for their use without testing must be obtained.

Previously approved materials transferred from another project should be reported on Form 2415. The report should include: type of material, quantities involved, source, and supplier of materials. Whenever possible, include the project number for which the material was originally approved.

A TELEPHONE INDEX is included with the Schedule giving the numbers of contact persons if further information is required regarding the various materials.

PLEASE CONTACT THE Mn/DOT DISTRICT INDEPENDENT ASSURANCE INSPECTOR WHEN PROJECT STARTS TO PROVIDE THE PROPER SERVICING OF YOUR PROJECT.

**INDEX**  
**Materials Control Schedule**

<b>I. Grading and Base Construction Items</b>	<b>Page 1 thru 4</b>
<b>II. Bituminous Construction Items for Specification 2340</b>	<b>Page 5 thru 9</b>
<b>III. Bituminous Construction Items for Specification 2350/2360</b>	<b>Page 10 thru 14</b>
<b>IV. Bituminous Construction Items for Specification 2331</b>	<b>Page 15 thru 17</b>
<b>V. Concrete Construction Items</b>	<b>Page 18 thru 22</b>
<b>VI. Agricultural Items</b>	<b>Page 23 thru 25</b>
<b>VII. Chemical Items</b>	<b>Page 26</b>
<b>VIII. Metallic Materials and Metal Products</b>	<b>Page 27 and 28</b>
<b>IX. Miscellaneous Materials</b>	<b>Page 29</b>
<b>X. Pipe, Tile, and Precast/Prestressed Concrete Structures</b>	<b>Page 30 and 31</b>
<b>XI. Brick, Stone, and Masonry Units</b>	<b>Page 32</b>
<b>XII. Electrical and Signal Construction Items</b>	<b>Page 33 and 34</b>

## TELEPHONE INDEX FOR SCHEDULE OF MATERIALS CONTROL

<b>Part I. Page 1</b>	<b>Grading and Base</b> Dave Beberg (651) 779-5608
<b>Part II. Page 5</b>	<b>Bituminous - Spec. 2340</b> John Garrity (651) 779-5577
<b>Part III. Page 5</b>	<b>Bituminous - Spec. 2350/2360</b> John Garrity (651) 779-5577
<b>Part IV. Page 10</b>	<b>Bituminous - Spec. 2331</b> All Bituminous Items Outstate and Metro Deb Evans (651) 779-5578 Metro Only Dean Smith (651) 779-5280
<b>Part V. Page 13</b>	<b>Concrete</b> Steve Babcock (651) 779-5573
<b>Part VI. Page 18</b>	<b>Agricultural Items</b> Turf Establishment Leo Holm (651) 779-5086 Landscaping Elizabeth Walton (651) 779-5107
<b>Part VII. Page 21</b>	<b>Chemical Items</b> Jim McGraw (651) 779-5550
<b>Part VIII. Page 22</b>	<b>Metallic Materials and Metal Products</b> Sampling Steve Grover (651) 779-5540 Test Results Laboratory (651) 779-5560
<b>Part IX. Page 24</b>	<b>Miscellaneous Materials</b> Sampling Steve Grover (651) 779-5540
<b>Part X. Page 25</b>	<b>Pipe, Tile, and Precast/Prestressed Concrete Structures</b> Sections 1 thru 5 and 8 thru 10 Jim Kochsiek (651) 779-5534 Sections 6, 7 and 11 Sampling Chuck Howe (651) 779-5602 Test Results Laboratory (651) 779-5560
<b>Part XI. Page 27</b>	<b>Brick, Stone and Masonry Units</b> Steve Grover (651) 779-5540
<b>Part XII. Page 28</b>	<b>Electrical and Signal Construction Items</b> Sections 2, 4, 6, and 7 Steve Grover (651) 779-5540 Sections 1 and 5 Sue Lodahl (651) 582-1095

**SCHEDULE OF MATERIALS CONTROL**

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

**I. GRADING AND BASE CONSTRUCTION ITEMS**

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
1 . <b>GRADATION(5-692.210)</b> (a) Aggregate Surfacing (2118) (b) Aggregate Base (2211) (c) Aggregate Shoulders (2221) (d) Bituminous Treated Base (2204)	3138 & Check Proposal	Random Sampled (See Notes 1 and 2)	02154-02	None	
				None except (See Note 3)	
(e) Stabilizing Aggregate (2105)	3149 & Check Proposal				
(f) Binder Soil (3138.2B)	3146	2 per source (See Note 1)	21760-03	1 per source	5 kg (10 lb.)
(g) Granular Borrow Select Granular Borrow (2105)	3149 & Check Proposal	0-65,000 m <sup>3</sup> (LV) - minimum of 1/5,000 m <sup>3</sup> (LV) or 7, whichever is less 66,000-130,000 m <sup>3</sup> (LV) - minimum 10 required 131,000-260,000 m <sup>3</sup> (LV) - minimum 15 required 261,000 m <sup>3</sup> (LV) or more - minimum 1/20,000 m <sup>3</sup> (LV)  0-50,000 m <sup>3</sup> (CV) - minimum of 1/4,000 m <sup>3</sup> or 7, whichever is less 51,000-100,000 m <sup>3</sup> (CV) - minimum 10 required 101,000-200,000 m <sup>3</sup> (CV) - minimum 15 required 201,000 m <sup>3</sup> (CV) or more - minimum 1/15,000 m <sup>3</sup> (CV)  1 m <sup>3</sup> (LV) =1.31 CuYd (LV) 1 m <sup>3</sup> (CV)=1.31 CuYd (CV) (See Note 1)		1 per source	10-15 kg (25 lb.)
(h) Granular Filter	3601 & Check Proposal	1 per source (See Note 1)			

**SCHEDULE OF MATERIALS CONTROL**

**I. GRADING AND BASE CONSTRUCTION ITEMS(Cont'd)**

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
(I) Granular Backfill (2451) (j) Aggregate Backfill (2451) (k) Granular Bedding (2451) (l) Aggregate Bedding (2451) (m) Coarse Filter (2451) (n) Fine Filter (2502) (o) Sand Cover (2206)	3149	1 per source (See note 1)	21760-03	1 per source	10-15 kg (25lb)
(q) Embankment Soil (Excavation and Borrow)	2105	None		1 per major soil for Identification (Specified Density Only)	5 kg (10 lb.)

No laboratory samples for 1,000 metric ton [1,000ton] or 600m<sup>3</sup> (LV) [714 CuYd (LV)] or 460m<sup>3</sup> (CV) [550 CuYd (CV)] or less.

First laboratory samples shall be taken within the first 3,000 metric ton [3,000 ton] and shall have a field companion sample.

LV = Loose Volume

CV = Compacted Volume

NOTE 1: No samples for 500 metric ton [500 ton] or less. Report on form 2415 or 2403 for small quantity.

NOTE 2: See Spec. 2211.3F for sampling procedures and Table 2211-A for Acceptance Testing Schedule and Tables 2211-B or 2211-C for payment schedules.

NOTE 3: If salvaged bituminous is used, submit separate bituminous extraction samples weighing 5 kg [10 lb.].

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>2. "ONE POINT DENSITY"</b> (5-692.583) (a) Bituminous Stabilized Subgrade	2207	1/ 1,500 m <sup>3</sup> (LV) or 1/1,200 m <sup>3</sup> (CV) or [1/2,000 CuYd (LV) or 1/1,500 CuYd (CV)]	24587 Retain in Field	None	
<b>3. MOISTURE-DENSITY TEST*</b> (5-592.222) (a) Aggregate Base	2211	1/40,000 t/source or [1/40,000 ton/source]	24587 Retain in Field	One sample minimum and additional samples as required	25-30 kg (50 lb.)
(b) Aggregate Shoulder	2221				
(c) Soil - Cement Base	2206	1/350 m <sup>3</sup> (LV) or 1/1,270 m <sup>3</sup> (CV) or [1/450 CuYd (LV) or 1/350 CuYd (CV)]		None	
(d) Embankment Soil	2105	1 per major soil.		Two samples per project and additional samples as required	

\*When Specified Density is Required.

**SCHEDULE OF MATERIALS CONTROL**

**I. GRADING AND BASE CONSTRUCTION ITEMS(Cont'd)**

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.**

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>4. RELATIVE DENSITY TEST** (5-692.251)</b>					
(a) Aggregate Base	2211	1/1,800 t, 1/1,000 m <sup>3</sup> (LV), or 1/800 m <sup>3</sup> (CV)	21760-03	None	
(b) Aggregate Shoulder	2221	<i>or</i> [1/1,800 ton, 1/1,300 CuYd (LV), or 1/1,000 CuYd (CV)]			
(c) Bituminous Stabilized Subgrade	2207				
(d) Soil - Cement Base	2206	1/350 m <sup>3</sup> (LV) or 1/270 m <sup>3</sup> (CV) <i>or</i> [1 per 450 CuYd (LV) or 1/350 CuYd (CV)]			
(e) Embankment Soil (Excavation and Borrow)	2105 & Check Proposal	1/3,000m <sup>3</sup> (LV) or 1/2,300 m <sup>3</sup> (CV) <i>or</i> [1/4,000 CuYd (LV) or 1/3,000 CuYd (CV)]			
<b>** When Specified Density if Required.</b>					
<b>5. RELATIVE MOISTURE TEST BEFORE PRIMING (5-692.253)</b>					
(a) Aggregate (2211)	2321 & 2358 Check Proposal	<u>Upper 75mm (3 in)</u> 1/350m <sup>3</sup> (LV) or 1/270 m <sup>3</sup> (CV)	21760-03	None	
(b) Aggregate Shoulder (2221)		<i>or</i> [1/450 CuYd (LV) or 1/350 CuYd (CV)]			
<b>6. RELATIVE MOISTURE TEST*** AT TIME OF COMPACTION (5-692.253)</b>					
(a) Aggregate Base	2211	1/1,800 t, 1/1,000 m <sup>3</sup> (LV) or 1/800 m <sup>3</sup> (CV)	21760-03	None	
(b) Aggregate Shoulder	2221	<i>or</i> [1/1,800 ton, 1/1,300 CuYd (LV), or 1/1,000 CuYd (CV)]			

**SCHEDULE OF MATERIALS CONTROL**

**I. GRADING AND BASE CONSTRUCTION ITEMS (Cont'd)**

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
(c) Bituminous Stabilized Subgrade (5-692.582) SS-1 Mixture	2207	1/1,000 m <sup>3</sup> (LV) or 1/800 m <sup>3</sup> (CV) <i>or</i> [1/1,300 CuYd (LV) or 1/1,000 CuYd (CV)]	21760-03	None	
(d) Soil - Cement Base	2206	1/350 m <sup>3</sup> (LV) or 1/270 m <sup>3</sup> (CV) <i>or</i> [1/450 CuYd (LV) or 1/350 CuYd (CV)]	21760-03	None	
(e) Embankment Soil (Excavation and Borrow) (5-692.253)	2105	1/2,000 m <sup>3</sup> (LV) or 1/1,500 m <sup>3</sup> (CV) <i>or</i> [1/2,600 CuYd (LV) or 1/2,000 CuYd (CV)]	21760-03	None	
<b>***When Specified Density is Required</b>					
<b>7. PULVERIZATION TEST (5-692.260)</b>					
(a) Binder Soil (3138)	3146	1 per day	21760-03	None	
(b) Soil - Cement Base	2206	1/350m <sup>3</sup> (LV) or 1/270 m <sup>3</sup> (CV) <i>or</i> [1/450 CuYd (LV) or 1/350 CuYd (CV)] 1/hour if plant mixed			
<b>8. PERCENT CRUSHING</b>					
(a) Belt Samples (5-692.203)	3138 & 3149	Once each day	02463 Retain in Field	None	10-15 kg (25 lb.)
(b) Particle Count (5-692.204)		One per Project			
<b>9. AGGREGATE (Quality Tests)</b>					
(Quality Tests)	3138	None		Submit sample of aggregate retained on the 4.75mm (#4) sieve from each source	25 kg (50 lb.)
				1 per source (Total Sample)	10-15 kg (25 lb.)

**SCHEDULE OF MATERIALS CONTROL**

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your Project.**

**II. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2340 (Note #1)  
(All bituminous mixtures are from Certified Plants)**

*DEFINITIONS*

SAMPLE TYPE	DESCRIPTION	SAMPLE LOCATION	SAMPLE TAKEN		SAMPLE TESTED
		DETERMINED BY	BY	BY	
QC	Quality Control Testing Performed by Contractor Also known as Process Control testing.	Contractor	Contractor		Contractor
QA	Quality Assurance Testing performed by the Agency. This test is performed on a companion sample to the Contractor's QC sample.	Contractor	Contractor		Agency
Verification	A sample which is sampled and tested by the Agency to assure compliance of the Contractor's Quality Control program.	Agency	Agency		Agency
Verification Companion	A companion sample to the Agency's verification sample provided to the Contractor. The Contractor <u>is required</u> to test this sample. The results <u>can be used</u> as part of the QC program.	Agency	Agency		Contractor
IAST	The <u>I</u> ndependent <u>A</u> ssurance <u>S</u> ampling and <u>T</u> esting assures testers are sampling and testing properly and that equipment is calibrated correctly.	Contractor or Agency	Contractor or Agency	Contractor or Agency	Contractor

**A. PRE-PRODUCTION SAMPLING AND TESTING for Specification 2340**

SAMPLE SIZE: 35 kg (75 lb.) for each aggregate type retained on 4.75mm (#4) sieve; for quality testing and Percent Crushing.  
2 kg (4 lb.) for each aggregate type passing the 4.75mm (#4) sieve; for quality testing.  
1kg (2 lb.) for mineral filler.

\*\*\*\*\*

**1. Bituminous Mix Design (QC/QA)**

**QC Testing**

1 per mix [3-point Asphalt Cement (AC) content]  
15 kg (35 lb.) of mixture at optimum asphalt content, plus 3 Marshall specimens.  
**REMARKS: Mix Design for Spec. 2340 is Contractor's responsibility with verification by Mn/DOT.**

**QA Testing**

Test Contractor's samples at optimum Asphalt Content, plus 3 Marshall specimens submitted along with Trial Mix data for Approval.



SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your Project.

II. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2340 (Note #1) (Part A, Cont'd)
(All bituminous mixtures are from Certified Plants)

2. Aggregate Quality Testing (QA Only)

QA Testing

Agency representative selects one (1) sample of each non-asphaltic aggregate type or class per source per year. When aggregate qualities approach specification limits or when material variation is observed, take additional field tests.

3. Mineral Filler (QA Only)

QA Testing

One (1) per shipment of 45 metric tons (50 tons) or less, unless previously inspected.

4. Additives (QA Only)

QA Testing

1 L (1 qt.) of blended bituminous material and additive. Sample first shipment of each type of material, then submit one sample per 1,000,000 L (250,000 gal.) (approx. 1,000 ton)

REMARK: Submit sample of additive at least one week before use.

NOTE 1: Projects with bituminous tonnage less than or equal to 272 metric tons (300 tons) per day may be accepted on a small quantity basis at the discretion of the Engineer. Retain Form 2415 or Form 2403 in Project File.

SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your Project.

II. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2340 (Note #1) (Cont'd)
(All bituminous mixtures are from Certified Plants)

B. BITUMINOUS PRODUCTION for Specification 2340

SAMPLE SIZE: 15 kg (35 lb.) for Aggregate for Gradation;
15 kg (35 lb.) for Mixture Properties
1 L (1 qt) for Asphalt Cement
2 L (1/2 gal) for Asphalt Emulsion

\*\*\*\*\*
1. Plant Mix Aggregate Gradation Testing (QC/QA)

QC Testing
1 per 1,360 metric tons (1,500 tons) per mix blend including non-asphaltic aggregate fraction from recycled mix with a minimum of 1 test per day.
Companion samples taken for agency for mixtures not containing salvaged asphaltic aggregate.

REMARKS: See Note #2 & Note #3

QA Testing
1 per day per mixture blend. (None from mixtures containing asphaltic aggregate.)
For Certified Plant: Agency representative will select one per day to be run as deemed necessary.

\*\*\*\*\*
2. Aggregate Percent Crushing (QC/QA)(Type 41, Type 42, Type 47, Type 48)

QC Testing
1 per 1,360 metric tons (1,500 tons) per mix blend minimum.
For Certified Plant: See Specification/Special Provisions for modifications.

REMARKS: See Note #3
None required when tonnage/course is less than 1,360 metric tons (1,500 tons).
Type 42 Tests run on non-asphaltic aggregate only.
Additional QA samples taken at discretion of the Engineer.

QA Testing
Agency representative is required to observe 1 per day per mixture blend.

\*\*\*\*\*
3. Spot Check (QC/QA)

QC Testing
1 per 1,360 metric tons (1,500 tons) per mix blend minimum; with a minimum of 1 test per day.

REMARKS: See Note #3
If a member of a monitoring team observes the Contractor test, note and sign under remarks.
The Project Engineer is responsible for:
1.) Reviewing control charts for accuracy and completeness.
2.) Checking, sampling and testing procedures.
3.) Discussing QC problem with Contractor.
4.) Obtaining verification samples.

QA Testing
1 per day per mixture blend conducted by plant monitor.
For Certified Plant: One per day minimum.

SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

II. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2340 (Note #1) (Part B, Cont'd)
(All bituminous mixtures are from Certified Plants)

4. Extraction and Gradation (QC/QA)

QC Testing

1 per 900 metric tons (1,000 tons) per mix blend for first 3,600 metric tons (4,000 tons) of mixture produced to verify mix design. Additional tests, at the same testing rate, required only when mixture property test results between Contractor and Agency are beyond the allowable differences as defined in Section .400 of the Mn/DOT Bituminous Manual or when either Contractor or Agency results fail specification criteria.

- e.g.: Individual air voids less than 2.0% or greater than 6.0%.
Moving average air voids less than 3.0% or greater than 5.0%.
Total extracted asphalt content below mixture type minimum or below recommendation target minimum.
Asphalt spot-check below mixture type minimum or below recommendation target minimum.
Extracted gradation beyond broad-band requirements.

REMARKS: See Note #2 & Note #3.
Extractions on Type 32, Type 42 and Type 48 mixtures only.
Testing at plant site is not required if approved by the Engineer.

QA Testing

1 per day per mixture blend.
For Certified Plant: Agency representative will select one per day.

5. Mixture Properties (QC/QA, Verification) (Maximum Gravity, Marshall Density-3 Specimen Average, Air Voids)

QC Testing

1 per 450 metric tons (500 tons) per mix blend for first 1,800 metric tons (2,000 tons) of mixture produced; then 1 per 900 metric tons (1,000 tons) with a minimum of 2 tests per day.
Verification Companion testing from Agency split sample is required to be performed and may be used as a QC sample.

REMARKS: See Note #2 & Note #3
Calibration factors shall be established regarding reheated samples.

QA Testing

An Agency representative is required to observe at least one QC test per day.

Verification Testing: An Agency representative will take 1 verification sample per mixture blend per day for Mn/DOT laboratory testing. A verification companion sample will be given to contractor for QC testing.

6. Core Density (Option 1)/Nuclear Density (Option 2) For Modified Specified Density Only

QC Testing

- 1 lot per day
5 sublots per lot
2 density determinations per subplot

REMARKS: Sawing of cores into separate lifts is required (Option 1). Contractor is required to have a saw capable of separating the core lifts without damaging the material at the field testing lab.

QA Testing

Option 1:
3 companion cores per lot per day for verification. Companion cores tested on Agency equipment. Agency representative observes all Contractor coring, sawing and testing, and takes possession of Mn/DOT cores after sawing. Agency cores shall be transported to the Laboratory (Agency field or District/Division) as soon as possible to prevent damage due to improper handling or exposure to heat.
For Certified Plant:
Agency representative observes weighing of cores in water and saturated surface dry weights.

SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

II. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2340 (Note #1) (Part B, Cont'd)
(All bituminous mixtures are from Certified Plants)

6. Core Density (Option 1)/Nuclear Density (Option 2) For Modified Specified Density Only (Cont'd)

Option 2:

For nuclear gauge calibration an Agency representative shall observe all Contractor testing and select 3 companion cores to verify Contractor's results for each mix design or change in mix design. Companion cores tested on Agency equipment. Agency representative observes all Contractor coring, sawing and testing, and takes possession of Mn/DOT cores after sawing. Agency cores shall be transported to the Laboratory (Agency field or District/Division) as soon as possible to prevent damage due to improper handling or exposure to heat.

Agency representative observes all nuclear density readings per lot per day.

\*\*\*\*\*

7. Nuclear Density Control Strip

QC Testing

Each Control Strip: 10 Random Tests
Each lot for Quality Level: 5 Random Tests

QA Testing

Agency representative observes all Contractor Testing

\*\*\*\*\*

8. Bituminous Materials including Asphalt Emulsion BITUMINOUS MATERIALS FROM A NON-CERTIFIED SOURCE ARE NOT ALLOWED

QC Testing

BITUMINOUS MATERIALS FROM A NON-CERTIFIED SOURCE ARE NOT ALLOWED

None except when Certified Plant.
For Certified Plant: Contractor assumes responsibility for sampling AC.

REMARKS: Pressure fit cans for cutback asphalt. Plastic jar with wide screw top for asphalt emulsion.

TACK MATERIAL

Certified Source - Sample only when material appears suspect

QA Testing

BITUMINOUS MATERIALS FROM A NON-CERTIFIED SOURCE ARE NOT ALLOWED

Asphalt Cement:

Sample first shipment of each type of material at the start of a plant's production each year or after set-up of a portable plant. Thereafter, submit one sample per 1,000,000 L (250,000 gal) (approx. 1,000 ton).

REMARKS: Contractor is responsible for sampling AC in certified plants.
Pressure fit cans for cutback asphalt. Plastic jar with wide screw top for asphalt emulsion.

Asphalt Emulsion:

Sample first shipment, then submit one sample per 200,000 L (50,000 gal.) (approx. 200 ton).

Tack Material:

Sample only when material appears suspect.

\*\*\*\*\*

9. Moisture Content in Mixture

QA Testing

When conditions are such (rainy weather and/or saturated stockpiles) that the Engineer suspects the mixture as sampled from behind the paver may have a moisture content exceeding 0.5%, a sample should be taken for each individual course and, at the discretion of the Engineer, tested according to the procedures in the Bituminous Manual (5-693.950). Moisture content above 0.5% are not allowed.

Note #2.

- All QA test samples shall be from split samples.
If a member of the monitoring team observes the Contractor Test, note and sign under remarks.
The Project Engineer is responsible for:
1.) Reviewing control charts for accuracy and completeness.
2.) Checking sampling and testing procedures.
3.) Discussing QC problems with the Contractor.
4.) Obtaining Verification Samples.
5.) When additional testing is necessary, collect QA samples which have been acquired and retained by the Contractor.

Note #3.

For process control testing, acceptance will be based on Contractor's test results as verified by Mn/DOT test results.

## SCHEDULE OF MATERIALS CONTROL

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your Project.**

### III. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2350/2360 (Note #1) (All bituminous mixtures are from Certified Plants)

#### DEFINITIONS

<u>SAMPLE TYPE</u>	<u>DESCRIPTION</u>	<u>SAMPLE LOCATION DETERMINED BY</u>	<u>SAMPLE TAKEN BY</u>	<u>SAMPLE TESTED BY</u>
QC	Quality Control Testing Performed by Contractor Also known as Process Control testing.	Contractor	Contractor	Contractor
QA	Quality Assurance Testing performed by the Agency. This test is performed on a companion sample to the Contractor's QC sample.	Contractor	Contractor	Agency
Verification	A sample which is sampled and tested by the Agency to assure compliance of the Contractor's Quality Control program.	Agency	Agency	Agency
Verification Companion	A companion sample to the Agency's verification sample provided to the Contractor. The Contractor <u>is required</u> to test this sample. The results <u>shall be used</u> as part of the QC program.	Agency	Agency	Contractor
IAST	The <u>I</u> ndependent <u>A</u> ssurance <u>S</u> ampling and <u>T</u> esting assures testers are sampling and testing properly and that equipment is calibrated correctly.	Contractor or Agency	Contractor or Agency	Contractor or Agency

#### A. PRE-PRODUCTION SAMPLING AND TESTING for Specification 2350/2360

SAMPLE SIZE: 35 kg (75 lb.) - plus #4 aggregate samle for quality testing and Percent Crushing  
 15 kg (35 lb.) - minus #4 aggregate for quality testing  
 15 kg (35 lb.) - bituminous mixture plus 3 Marshall specimens for volumetric testing (both options)\*  
 25 kg (55 lb.) - bituminous mixture for TSR testing (option #1)\*  
 8.2 kg (18 lb.) - bituminous mixture for TSR testing plus 6 Marshall specimens (option #2)\*  
 1 kg (2 lb.) - for mineral filler.

\* There are two options in Specification 2350 for bituminous mix design.

SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your Project.

III. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2350/2360 (Note #1) (Part A, Cont'd)
(All bituminous mixtures are from Certified Plants)

\*\*\*\*\*

1. Bituminous Mix Design (QC/QA)

QC Testing

1 per mix [3-point Asphalt Cement (AC) content]
15 kg (35 lb.) of mixture at optimum asphalt content plus 3 Marshall specimens.
50 kg (110 lb.) of mixture at optimum asphalt content plus 2 gyratory specimens.

REMARKS: Mix Design for Spec. 2350/2360 is Contractor's responsibility with verification by Mn/DOT.

QA Testing

Test Contractor's samples at optimum Asphalt Content, TSR, plus 3 Marshall specimens submitted along with Trial Mix data for Approval.
Test Contractor's samples at optimum Asphalt Content, TSR, plus 2 gyratory specimens submitted along with Trial Mix data for Approval.

\*\*\*\*\*

2. Aggregate Quality Testing (QA Only)

QA Testing

Contractor shall provide 24 hour notice of intent to sample aggregates for quality testing. Agency has the option to monitor sampling.
Contractor submits to the Bituminous Engineer or the District Materials Engineer one (1) sample of each non-asphaltic aggregate type or class per source per year. When aggregate qualities approach specification limits or when material variation is observed, take additional field tests.

\*\*\*\*\*

3. Mineral Filler (QA Only)

QA Testing

One (1) per shipment of 45 metric tons (50 tons) or less, unless previously inspected.

\*\*\*\*\*

4. Additives (QA Only)

QA Testing

1 L (1 qt.) of blended bituminous material and additive. Sample first shipment of each type of material, then submit one sample per 1,000,000 L (250,000 gal.) (approx. 1,000 ton)

REMARK: Submit sample of additive at least one week before use.

NOTE 1: Projects with bituminous tonnage less than or equal to 272 metric tons (300 tons) per day may be accepted on a small quantity basis at the discretion of the Engineer. Retain Form 2415 or Form 2403 in Project File.

SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your Project.

III. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2350/2360 (Note #1) (Cont'd)
(All bituminous mixtures are from Certified Plants)

B. BITUMINOUS PRODUCTION for Specification 2350/2360

- SAMPLE SIZE: 15 kg (35 lb.) for Aggregate for Gradation; 25 kg (55 lb.) for 2350 Mixture Properties 35 kg (75 lb.) for 2360 Mixture Properties 50 kg (110 lb.) for TSR 40 kg (90 lb.) for Aggregate Specific Gravity 1 L (1 qt) for Asphalt Cement 2 L (1/2 gal) for Asphalt Emulsion

1. Plant Mix Aggregate Gradation Testing (QC/QA)

QC Testing

1 per 2,000 metric tons (2,200 tons) or portion thereof per mix blend as required by 2350.5C3a(6)(a)(b) or 2360.4E6a 1 per 500 metric tons (550 tons) when operating under corrective action. Companion samples taken for agency.

REMARKS: See Note #2 & Note #3

QA Testing

Companion samples to QC samples set aside for 7 days and tested as needed.

2. Aggregate Percent Crushing (QC/QA)

QC Testing

Testing rates as required by 2350.5C3B, 2360.4E9 CAA, 2360.4E10 FAA. Two tests per day (CAA, FAA) for first two days. If CAA results exceed the specification minimum by 8% of the requirement; sample daily, test minimum one per week. If FAA results exceed the specification minimum by 5% of the requirement; sample daily, test minimum one per week.

REMARKS: See Note #3

QA Testing

Companion samples to QC samples set aside for 7 days and tested as needed.

3. Asphalt Content, % (QC/QA)

QC Testing

Divide planned production by 1,000; round up to determine testing rate.

- (a) Meter Method (Virgin only) Mn/DOT Bituminous Manual
(b) Incinerator Oven Mn/DOT Lab Manual Method 1853
(c) Extraction Mn/DOT Lab Manual Method 1851 or 1852
(d) Spot Check (Virgin only) Mn/DOT Bituminous Manual 5-693.848

REMARK: The verification companion sample must use Method (b) or (c) only.

When more than one Mn/DOT approved test procedure is available, the Contractor shall select one method at the beginning of the project (when material submitted for Trial Mix Verification) and use that method for the entire project. The Contractor and Engineer may agree to change test procedures during the construction of the Project.

REMARKS: See Note #3

If a member of a monitoring team observes the Contractor test, note and sign under remarks.

The Project Engineer is responsible for:

- 1.) Reviewing control charts for accuracy and completeness.
2.) Checking, sampling and testing procedures.
3.) Discussing QC problem with Contractor.
4.) Obtaining verification samples.

QA Testing

Companion samples to QC samples set aside for 7 working days and tested as needed.

SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

III. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2350/2360 (Note #1) (Part B, Cont'd) (All bituminous mixtures are from Certified Plants)

\*\*\*\*\*

4. Mixture Properties (QC/QA, Verification) (Maximum Gravity, Marshall Bulk Gravity - 3 Specimen Average, Gyrotory Bulk Gravity - 2 Specimen Average)

QC Testing
1 per 450 metric tons (500 tons) per mix blend for first 1,800 metric tons (2,000 tons) of mixture produced.
Divide planned production by 1,000; round up to determine testing rate.
Verification Companion testing from Agency split sample is required to be performed and shall be used as a QC sample once per day.

REMARKS: See Note #2 & Note #3
Calibration factors shall be established regarding reheated samples.

QA Testing
Companion samples to QC samples set aside for 7 working days and tested as needed.
The agency representative is required to observe at least one QC test per day.

Verification Testing
Verification Companion testing from Agency split sample is required to be performed and shall be used as a QC sample once per day. Verification testing to include the following Mixture Properties; Maximum Gravity, Marshall Bulk Gravity - 3 Specimen Average or Gyrotory Bulk Gravity - 2 Specimen Average, air voids, V.M.A., % crushing, A.C. content, and gradation.
An Agency representative will take 1 verification sample per mixture blend per day for Mn/DOT laboratory testing. A verification companion sample will be given to contractor for QC testing.

\*\*\*\*\*

5. Core Density and Thickness

QC Testing
Refer to Tables 2350-7 or 2360-15 for production/lot testing rate requirements.

REMARKS: Sawing of cores into separate lifts is required (Option 1). Contractor is required to have a saw capable of separating the core lifts without damaging the material at the field testing lab.

QA Testing
1 companion core per lot. Companion core locations determined by Agency. Agency takes possession of cores after sawing. Agency cores shall be transported and tested at the Laboratory (Agency field or District/Division) as soon as possible to prevent damage due to improper handling or exposure to heat.

\*\*\*\*\*

6. Aggregate Specific Gravity (QC/QA)

QC Sampling
1 per 10,000 metric tons (11,000 tons). Tested by Contractor, if requested by Project Engineer.

QA Testing
Companion sample to QC sample shall be submitted to the District/Division Materials Lab and tested as needed.

\*\*\*\*\*

7. Tensile Strength Ratio (T.S.R.) (QC/QA)

QC Sampling
1 per 10,000 metric tons (11,000 tons). Tested by Contractor, if requested by Project Engineer

QA Testing
Companion sample to QC sample shall be submitted to the District/Division Materials Lab and tested as needed.



SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

III. BITUMINOUS CONSTRUCTION ITEMS FOR SPECIFICATION 2350/2360 (Note #1) (Part B, Cont'd)
(All bituminous mixtures are from Certified Plants)

\*\*\*\*\*

8. Bituminous Materials including Asphalt Emulsion

QC Sampling

None except when Certified Plant.
For Certified Plant: Contractor assumes responsibility for sampling AC. (2350.5C3f or 2360.4E12)

REMARKS: Pressure fit cans for cutback asphalt.
Plastic jar with wide screw top for asphalt emulsion.

TACK MATERIAL
Certified Source - Sample only when material appears suspect

BITUMINOUS MATERIALS FROM A NON-CERTIFIED SOURCE ARE NOT ALLOWED.

QA Testing

CERTIFIED SOURCE:
Asphalt Cement Only
Sample first shipment of each type of material, then submit one sample per 1,000,000 L (250,000 gal) (approx. 1,000 ton)

CERTIFIED SOURCE:
Asphalt Emulsion Only
Sample first shipment, then submit one sample per 200,000 L ((50,000 gal.) (approx. 200 ton)

\*\*\*\*\*

9. Moisture Content in Mixture (QC only)

QC Testing

When conditions are such (rainy weather and/or saturated stockpiles) that the Engineer suspects the mixture as sampled from behind the paver may have a moisture content exceeding 0.3%, a sample should be taken for each individual course and, at the discretion of the Engineer, tested according to the procedures in the Bituminous Manual (5-693.950). Moisture content above 0.3% are not allowed.

Note #2. All QA test samples shall be from split samples.
If a member of the monitoring team observes the Contractor Test, note and sign under remarks.
The Project Engineer is responsible for:
1.) Reviewing control charts for accuracy and completeness.
2.) Checking sampling and testing procedures.
3.) Discussing QC problems with the Contractor.
4.) Obtaining Verification Samples.
5.) When additional testing is necessary, collect QA samples which have been acquired and retained by the Contractor and/or additional verification samples.

Note #3.
For process control testing, acceptance will be based on Contractor's test results as verified by Mn/DOT test results.

**SCHEDULE OF MATERIALS CONTROL**

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.**

**IV. BITUMINOUS CONSTRUCTION ITEMS FOR PROJECTS CONSTRUCTED UNDER SPECIFICATION 2331 (See Note #1)**

**A. PRE-PRODUCTION SAMPLING AND TESTING for Specification 2331**

Contractor Trial Mix Design and Verification      35 kg (75 lb.) for each aggregate type retained on 4.75mm (#4) sieve; for quality testing, and percent crushing.  
 2 kg (4 lb.) for each aggregate type passing the 4.75 mm (#4) sieve; for quality testing.

Material	Spec. Mix	Rate of Field Testing	Form No.	Sampling Rate for Laboratory Testing	Sample Size
1. Trial Mix for Bituminous Content Recommendations	2331 3139	None	None	The Contractor will submit a representative sample from each source	135kg (300 lb.) of total blend with a minimum 45kg (100 lb.) of each component

-or-

Contractor's Mix Design      15 kg (35 lb.) of mix  
 Defined for Aggregate Preproduction (listed above)

**REMARKS: Contractor's mix design sample at optimum asphalt content plus 3 Marshall specimens with Trial Mix data for approval**

**B. BITUMINOUS PRODUCTION for Specification 2331**

1. Aggregate (Gradation) A. Plant Mix Aggregate	2331 Type 31 Type 41 Type 47 Type 61 3139	<u>1 per 900 metric tons (1,000 tons) per mix blend</u> No field tests required for quantity less than 272 metric tons (300 tons) per mix type when from previously accepted source. Use form 2415 or 2403.	TP 24449	1 per 9,000 metric tons (10,000 tons) If Field samples are tested in District Laboratory, separate laboratory testing at 1 per 9,000 metric tons (10,000 tons) is not required.	10 kg (25 lb.)
--	--	---	----------	--	----------------

**REMARKS:**  
 No routine laboratory samples required for quantities less than 900 metric tons (1,000 tons) mix.  
 Quantities shown for laboratory samples refer to total tons of bituminous mixtures on project.  
 All laboratory samples shall have field companions.  
 If test results do not comply with Job Mix Formula gradation values, two samples shall be taken and tested on the succeeding day.

B. Mineral Filler	3145	None	None	1 per shipment of 45 metric tons (50 tons) or less unless previously inspected.	1 kg (2 lb.)
C. Seal Coat	3127	1 per 400 m <sup>3</sup> (500 CuYd)	TP 2429	1 per 1,500 m <sup>3</sup> (2,000 CuYd)	10 kg (25 lb.)

**REMARKS:**  
 First sample within first 800 m<sup>3</sup> (1,000 CuYd) production. No routine laboratory samples required for quantity less than 800 m<sup>3</sup> (1000 CuYd)

2. Aggregate (% Crushing)	2331 Type 41 Type 42 Type 47 Type 48 3139	<u>1 per 1,350 metric tons (1,500 ton) per mix blend with a minimum of 1 per day</u>	TP 7119-02		
---------------------------	--	--	------------	--	--

**REMARKS:**  
 None required when tonnage/course is less than 1,350 metric tons (1,500 tons).  
 If test results do not comply with Specifications; 2 samples shall be taken and tested on the succeeding day.  
 For Type 42, tests will be run on non-asphaltic aggregate only.

**SCHEDULE OF MATERIALS CONTROL**

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.**

**IV. BITUMINOUS CONSTRUCTION ITEMS FOR PROJECTS CONSTRUCTED UNDER SPECIFICATION 2331 (See Note #1) (Part B, Cont'd)**

Material	Spec. Mix	Rate of Field Testing	Form No.	Sampling Rate for Laboratory Testing	Sample Size	
*****						
3. Aggregate (Quality Tests)	2331	When spall content is near upper limits, take additional field tests.	TP 2429	1 sample of each non-asphaltic aggregate type or class per source per year. When aggregate qualities approach specification limits or when material variation is observed take additional field tests.	35 kg (Note A.) (75 lb.)	
	3139				2 kg (Note B.) (4 lb.)	
Note A.- Sample of aggregate retained on 4.75mm (#4) sieve Note B. - Sample of aggregate passing the 4.75mm (#4) sieve *****						
4. Bituminous Materials (Including Asphalt Emulsion)	2331	None	None	<u>CERTIFIED SOURCE:</u> Asphalt Cement Only Sample first shipment of each type of material, then submit one sample per 1,000,000 L (250,000 gal) (approx. 1,000 ton)	1 L (1 quart)	
	2356				<u>CERTIFIED SOURCE:</u> Asphalt Emulsion Only Sample first shipment, then submit one sample per 200,000 L (50,000 gal) (Approx. 200 ton)	2 L (½ gal)
	2357					
	2358					
3151						

**REMARKS: BITUMINOUS MATERIALS FROM A NON-CERTIFIED SOURCE ARE NOT ALLOWED.**  
**Pressure fit cans for AC and Cutback AC samples.**  
**Wide mouth plastic jars with screw covers for Asphalt Emulsion.**  
**TACK MATERIALS: Sample only when material appears suspect.**  
 \*\*\*\*\*

**5. Bituminous mixtures (Plant Mixed)**

A. Asphalt Content by Spot Check method	2331	As often as required to control 1 per day minimum	TP 24448-01	None
B. Density (Specified Density)	2331	Marshall Density: Daily, Minimum 1 per 900 metric tons (1,000 tons) per course.  Core Density: Daily, Minimum 1 per 900 metric tons (1,000 tons) per course	TP 24447-02	None

**REMARKS: Samples shall be taken from each day's production at the direction of the Engineer, prior to placement of the next course thereon and not later than the next working day following the date of placement.**

C. Density (Control Strip)	2331	(1) Each Control Strip: 10 Random Tests. (2) Each Lot for Quality Control 5 Random Tests.	TP 24342 TP 24446-01	None
D. Extraction and Gradation Recycled Mixtures Only Under Spec 2331	Type 32 Type 42 Type 48 <u>and</u> all mixes measured by square yard inch	None		2 per mixture blend on first day of production.  1 per mixture blend per day thereafter.

**REMARKS: Sample shall be taken from mixture property test(s). If test results do not comply with Job Mix Formula gradation values, a minimum of 2 samples each succeeding day until test results comply with Job Mix Formula gradation values.**

**SCHEDULE OF MATERIALS CONTROL**

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project**

**IV. BITUMINOUS CONSTRUCTION ITEMS FOR PROJECTS CONSTRUCTED UNDER SPECIFICATION 2331 (See Note #1) (Part B, Cont'd)**

Material	Spec. Mix	Rate of Field Testing	Form No.	Sampling Rate for Laboratory Testing	Sample Size
<b>5. Bituminous Mixtures (Cont'd)</b>					
<b>(Plant Mixed)</b>					
E. Mixture Properties	2331	None		1 per 450 metric tons (500 tons) per mix blend for first 1800 metric tons (2,000 tons) of mix produced then 1 test per mix per day.	10 kg (25 lb.)
				FOR SQUARE YARD INCH PROJECTS 2 per mixture blend on first day 1 per mixture blend per day thereafter.	

**REMARKS:**

**If testing rate for first 1,800 metric tons (2,000 tons) of production has been satisfied on previous project and continuous production of the mix type has been established, then 1 test per mix per day.**

**Samples should be taken from behind paver.**

**If test results do not comply with mix design air voids criteria, additional samples shall be taken and tested at the rate of 1 per 450 metric tons (500 tons) each succeeding day until test results comply with mix design criteria. The samples shall weigh approximately 10 kg (25 lb.) (Small sample bag or concrete cylinder mold).**

**If the appearance of the mixture changes, additional samples should be taken.**

*****					
<b>6. Additives</b>	3161	None		1 L (1 qt) sample of blended bituminous material and additive. Sample first shipment of each type of material, then submit one sample per 1,000,000 L (250,000 gal.) (approx. 1,000 ton)	
*****					
<b>7. Moisture content in Mixture</b>	2331	When conditions are such (rainy weather and/or saturated stockpiles) that the Engineer suspects that the mixture as sampled from behind the paver may have a moisture content exceeding 0.5%, a sample should be taken for each individual course and, at the discretion of the Engineer, tested according to the procedures in the Bituminous Manual (5-693.950)			

Moisture contents above 0.5% are not allowed.

---

**Note #1: Projects with bituminous tonnage less than or equal to 272 metric tons (300 tons) per day may be accepted on a small quantity basis at the discretion of the Engineer. Document on Form 2403 or Form 2415 and retain in project file.**

---

**SCHEDULE OF MATERIALS CONTROL**

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.**

**V. CONCRETE CONSTRUCTION ITEMS  
(All Ready Mix is from Certified Plants)**

*DEFINITIONS*

<u>SAMPLE TYPE</u>	<u>DESCRIPTION</u>	<u>SAMPLE LOCATION DETERMINED BY</u>	<u>SAMPLE TAKEN BY</u>	<u>SAMPLE TESTED BY</u>
QC	Quality Control Testing Performed by Contractor Also known as Process Control testing.	Contractor	Contractor	Contractor
QA	Quality Assurance Testing performed by the Agency. This test is performed on a companion sample to the Contractor's QC sample. <b>If QA only, sampling and testing by Agency only.</b>	Contractor	Contractor	Agency
Verification (Audit Sample)	A sample which is sampled and tested by the Agency to assure compliance of the Contractor's Quality Control program.	Agency	Agency	Agency
Verification Companion	A companion sample to the Agency's verification sample provided to the Contractor. The Contractor <u>is required</u> to test this sample. The results <u>are required to be used</u> as part of the QC program	Agency	Agency	Contractor
IAST	The <u>I</u> ndependent <u>A</u> ssurance <u>S</u> ampling and <u>T</u> esting assures testers are sampling and testing properly and that equipment is calibrated correctly.	Agency	Contractor or Agency	Contractor or Agency

**PAVING PLANT** - Central Batching Plant dedicated to a concrete paving project delivering concrete other than by Ready-Mix trucks.

**A. CONCRETE AGGREGATE TESTING (All Concrete) Specification 3126, 3128 and 3137.**

SAMPLE SIZE: 10 - 15 kg (25 lb.) for +19 mm (3/4" Plus) Coarse Aggregate  
5 - 7 kg (10-15 lb.) for -19 mm (3/4" Minus) Coarse Aggregate  
5 kg (10 lb.) for CA-70 and Sand

**1. Certified Ready Mix Concrete: QC/QA Only**

a. Gradation Testing

- 1) QC Testing - When over 20 m<sup>3</sup> (CuYd) of agency concrete produced per day
  - Coarse: 1 per 100 m<sup>3</sup> (CuYd) of concrete
  - Fine: 1 per 200 m<sup>3</sup> (CuYd) of concrete
- 2) QA Testing

Coarse and Fine: For plants producing over 500 m<sup>3</sup> (500 CuYd) of Certified production each day, take verification (audit) samples at a rate of 1 per day. For plants producing 20 m<sup>3</sup> to 500 m<sup>3</sup> (20 CuYd to 500 CuYd) of Certified production each day, take verification (audit) samples at a rate of 1 per 500 m<sup>3</sup> (500 CuYd) based on an accumulative (day-to-day) basis. Take a minimum of 1 verification (audit) sample per week. Take a maximum of 3 verification (audit) samples per week for higher production. Take more verification (audit) samples when QC/QA problems exist. QA Coarse Aggregate testing on -75µm (#200) material as directed by the Engineer

*Note: As a check on field testing equipment when QA testing is performed in the field, send one split gradation sample per month to District Lab for comparison testing.*

SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.

V. CONCRETE CONSTRUCTION ITEMS (Part A, Cont'd)
(All Ready Mix is from Certified Plants)

- b. Moisture Testing
1) QC Testing - When over 20 m³ (CuYd) of agency concrete produced per day
Coarse and Fine: 1 per 200 m³ (CuYd) of concrete
2) QA Testing - None Required. Testing Rate at the Discretion of the Engineer

- c. Quality Testing
1) QC Testing - At Contractor's discretion
2) QA Testing - Sampled for acceptance (QA) at the rate of 1 per month. Testing rate may be adjusted by contacting the Concrete Office.

2. Paving Concrete

See Special Provisions for QA/QC testing schedule on projects with a dedicated Contractor paving plant ; otherwise, the testing rate for Certified Ready Mix Concrete applies.

NOTE: When work requires that a Certified Ready Mix Concrete Plant be dedicated to a paving project, a full-time plant monitor and daily audit samples are recommended. The Contractor sampling and testing rate may be reduced with the approval of the Concrete Office.

3. Low Slump Concrete for Overlay and Concrete Pavement Repair (QA Only)

- a. Gradation
QA Testing - 1 per fraction prior to commencing operations and each time aggregate is delivered to site.
Quality testing as directed by the Engineer

B. STRUCTURAL CONCRETE CONTROL TESTS (Specification 2461 and 2301)

Note: If Contractor Quality Control (QC) is required, it will be included in the Special Provisions

1. Certified Ready Mix Concrete (Other than concrete from a Paving Plant)

NOTE: For Concrete Paving from Certified Ready Mix Plants, the sampling and testing rate as listed below shall apply unless reduced with approval of the Concrete Office.

- a. Air Content and Slump
QA Only
Test first load or pour each day. After the first test, then 1 test per 100 m³ (CuYd)
b. Strength (See Notes #1 and #2)
QA Only
1 per 100 m³ (CuYd)
1 per day minimum if production is more than 20 m³ (CuYd)

Note #1: For concrete mixtures containing aggregate with a maximum size of 31.5 mm (1 1/4 in.), 100 mm x 200 mm (4 in x 8 in) cylinders may be substituted for 150 mm x 300 mm (6 in x 12 in) cylinders.

Note #2: Additional Control Cylinders as necessary.

2. Paving Concrete from Paving Plants (For Paving Concrete from Ready-Mix Plants, the sampling and testing rate for Certified Ready Mix Concrete shall apply unless reduced with the approval of the Concrete Office.) See Special Provisions for sampling and testing rates for dedicated paving plants.

- a. Air Content and Slump
NOTE: Only one slump test per day is required on slipform paving. See Certified Ready Mix Concrete testing rates when paving concrete is supplied by ready-mix.

QA Only
Test first load each day. After the first test, then 1 test per 300 m³ (CuYd)

**SCHEDULE OF MATERIALS CONTROL**

**Please contact the Mn/DOT District Independent Assurance Inspector when project starts to provide servicing of your project.**

**V. CONCRETE CONSTRUCTION ITEMS (Part B, Cont'd)  
(All Ready Mix is from Certified Plants)**

\*\*\*\*\*

**2. Paving Concrete (Cont'd)**

- b. Strength  
QA Only  
1 set of two beams per 2,000 m<sup>3</sup> (2,500 CuYd)

**REMARKS: If less than 2,000 m<sup>3</sup> (2,500 CuYd) of paving, a set of 2 cylinders per day may be substituted for the beam requirements.  
NOTE: Additional Control Beams as necessary.**

- c. Thickness  
QC/QA Testing

CONTRACTOR TAKES ONE RANDOM CORE PER 1,000 ft (300 m)/TRAFFIC LANE/5,000 ft (1,500 m) or SECTION

CORES FOR VERIFICATION: (See specification 2301.3P2 for procedure). The Contractor provides the cores. The cores are taken at locations determined by the Project Staff using Random Numbers. The Project Staff initials pavement at core locations and reinitials the sides of specimens after coring to clearly verify their authenticity.

- d. Smoothness  
QC Testing

CONTRACTOR PROVIDES CALIFORNIA'S PROFILOGRAPH RESULTS

\*\*\*\*\*

**3. Low Slump Concrete for Overlay and Concrete Pavement Repair (CPR) QA Only**

- a. Air content and slump: Test at beginning of pour each day, then 1 per 15 m<sup>3</sup> (Cu Yd)
- b. Strength : 1 per 30 m<sup>3</sup> (Cu Yd) - 1 minimum

**REMARKS: For low-slump concrete from concrete mobile, allow mix to hydrate 4 to 5 minutes before slump test to assure all cement is saturated.**

\*\*\*\*\*

**C. CEMENT**

\*\*\*\*\*

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
1. STANDARD PORTLAND High Early Portland Air Entraining Portland Air Entraining High Early Portland	3101	24300	Certified Cement*		2 kg (5 lb.)
2. PORTLAND-POZZOLAN Blended Cement Ground Granulated Blast Furnace Slag (GGBFS)	3103			Certified Source*	2 kg (5 lb.)
3. FLY ASH	3115			Certified Fly Ash*	2 kg (5 lb.)

**REMARKS:** All certified products must so state on the Bill of Lading.  
 1. All Cement and Fly Ash must be certified by the Lab before use.  
 2. Suggested Spot Check sampling rates for  
 a. CONCRETE PAVING PROJECTS  
 1 Sample per 10,000 CuYd. of Concrete (Minimum of 1 per project)  
 b. FOR OTHER CONCRETE  
 1 Sample every 2 to 4 weeks per plant as production warrants.

**NOTE:** \* No routine sampling required. Spot Check sampling as District Materials Engineer directs.

## SCHEDULE OF MATERIALS CONTROL

Please contact the Mn/DOT District Independent Assurance Inspector when Project starts to provide servicing of your project.

## V. CONCRETE CONSTRUCTION ITEMS (Cont'd)

\*\*\*\*\*

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>D. CURING MATERIALS</b>					
1. Burlap	3751	Visual Inspection	2150-4 Daily	1 per shipment	1 m <sup>2</sup>
2. Membrane Compound	3754 3754 AMS 3755		Concrete Data	1 sample for each shipment or if shipment contains more than 1 lot, sample each lot. SEE REMARKS	½ L (1 pt.)
<b>REMARKS: Material must be thoroughly stirred or agitated immediately prior to taking sample. Cover sample immediately. Call (651) 779-5556 before sampling.</b>					
3. Paper or Plastic	3752 3756	Visual Inspection	2150-4	1 per shipment	0.25 m <sup>2</sup> (2 Sq Ft)
<b>NOTE: Must be white opaque.</b>					
<b>E. JOINT MATERIALS</b>					
1. Hot Poured Elastic Type	3720 3723 3725	Visual Inspection		1 per lot	5 kg (10 lb.)
<b>Usually inspected at source. Call Laboratory at (651) 779-5548 for approval.</b>					
2. Silicone Joint Sealer				Approved Products Only*	
<b>*Approved products only. No routine sampling required. Spot Check sampling as District Materials Engineer directs.</b>					
3. Preformed Elastomeric Type	3721	Visual Inspection	2415*	1 per 1,000 m (3,000 LF) for or 2403 each lot or sub-lot or fraction	2 m (6 ft)
<b>* Field Inspection Report (Lot Numbers Only)</b>					
4. Preformed	3702	Visual Inspection		1 per shipment of each type and thickness	0.25 m <sup>2</sup> (2 SqFt)
<b>Will carry "Inspected" tag if approved prior to shipment.</b>					
<b>F. ADMIXTURES FOR CONCRETE</b>					
Accelerating, Retarding, Water Reducing, Air Entraining.	3113	Visual Inspection		1 per shipment for each type, brand and concentration.	.25 L (½ pt.) in Plastic Container
<b>APPROVED PRODUCTS ONLY</b>					
<b>G. CONCRETE TREATING OIL</b>					
	3917	Visual Inspection		1 per shipment	.5 L (1pt.) in Steel Container
<b>H. WATER</b>					
	3906	Visual Inspection		1 sample from any questionable source. Use clean glass or plastic containers.	3.5 L (1 gal)



**SCHEDULE OF MATERIALS CONTROL**

**Please contact the Mn/DOT District Independent Assurance Inspector when Project starts to provide servicing of your project.**

**V. CONCRETE CONSTRUCTION ITEMS (Cont'd)**

\*\*\*\*\*

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>I. EPOXIES</b>		Visual Inspection		1 sample of each component from each lot in each shipment for quantities over 1 gallon	.25 L (½ pt.) of each component in Steel Container
<b>Must be approved prior to use.</b>					

*There are certain items of concrete which are acceptable under a modified small quantity acceptance plan from a known and reliable source. These small quantities should be documented by the Engineer but no inspection reports are necessary.*

**FIELD TESTING (No Plant Inspection):**

- Field Testing, 1 air, (if required), 1 slump and 1 cylinder test per day:
  - 1 - 20 m<sup>3</sup> (CuYd) of general concrete work (pavement, curb and gutter, bridge footings, bridge concrete constructed above footings, median barrier, etc.)
  - 1 - 100 m<sup>3</sup> (CuYd) of concrete of a non-critical nature (all Grade C concrete, C. I. P. pile filling, fence post footings, etc.)

**PLANT TESTING (No Field Inspection):**

- 1 Delivery truck load for all types of work may be accepted without field tests if all plant tests are performed, including batching and mixing inspection.

*Should unique circumstances arise on a project which makes the above quantities or rates of testing for concrete shown elsewhere impractical, they may be revised prior to performing the work by contacting the Concrete Engineering Section and obtaining their approval.*

**SCHEDULE OF MATERIALS CONTROL**

**VI. AGRICULTURAL ITEMS**

Kind of Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
*****					
1. Plant Installation Materials	3861	Field Inspection at Job Site. Submit itemized report for each shipment. Include Mn/DOT Certificate of Compliance for plant stock, plant stock labels, invoices, Dept. of Agriculture Certificate of Nursery Inspection, Gypsy Moth & Japanese Beetle Certificate of Compliance.	2415 or 2403		
<b>REMARKS: Preliminary inspection will not be done at the source. Material must be in accordance with the Inspection and Contract Administration Guidelines for Mn/DOT Landscape Projects.</b>					
*****					
2. Fertilizer	3881	Visual Inspection			
<b>REMARKS:</b> <b>BAGGED: Inspected on the basis of guaranteed analysis.</b> <b>BULK: Inspector to verify analysis by checking weight tickets of blended material.</b>					
*****					
3. Agricultural Lime	3879	One gradation test for each 180 Metric Ton (200 ton)	2415 or 2403	One sample per source for quantities of 90 metric ton (100 ton) or less	4.5 kg (10 lb.)
<b>REMARKS: Submit form 2415 or 2403. Small Quantity is 90 metric ton (100 ton) or less.</b>					
*****					
4. Topsoil Borrow	3877.2A	None.		From each source: One composite sample for the first 765 m <sup>3</sup> (1,000 CuYd) or less. One composite sample for each additional 2,300 m <sup>3</sup> (3,000 CuYd) or fraction thereof.	10 kg (20 lb.)
<b>REMARKS: Testing takes about three weeks after delivery of the sample to the Department Laboratory. Sampling shall be done prior to the time the topsoil is delivered to the project.</b>					
<b>Small Quantity - 230 m<sup>3</sup> (300 CuYd)</b>					
*****					
5. Select Topsoil Borrow	3877.2B	None.		Same as Topsoil Borrow above	10 kg (20 lb.)
<b>REMARKS: Testing takes about <u>four</u> weeks. See remarks for Topsoil Borrow.</b>					
*****					
6. Seeds	3876				
A. Certified Vendors only		Check for guaranteed analysis labels. Check for variety and county of origin for native seeds.	2415 or 2403	Sampling need only be done for seed that is moldy or seed not planted within nine months after germination test, or if quantity used is more than 450 kg (1,000 lb.)	.5 L (1 pint)

**REMARKS: Seed guaranteed as meeting the requirements is identified by official guaranteed analysis labels affixed to each container of seed in addition to the customary seed tag. Submit copy of seed tag to Materials Lab. Indicate quantity used and contractor.**

**SCHEDULE OF MATERIALS CONTROL**

**VI. AGRICULTURAL ITEMS (Cont'd)**

Kind of Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>6. Seeds (Cont'd)</b>					
B. Non-Certified Vendors	3876		2415 or 2403	MUST BE SAMPLED. For 25 bags or less, combine from five bags (1 pint) into one sample. For larger quantities; sample each 5th bag combine samples into groups of 5 and select a test sample from each composite.	.5 L

**REMARKS: Submit samples six weeks before seeding to allow for testing. May be samples at source by laboratory upon proper notification.**

**Small Quantity - 90 kg (100 lb.)**

C. Wildflower Seed	3876	Check if from Certified Vendor or Approved Source		85 gm	(3 oz)
--------------------	------	---	--	-------	--------

**REMARKS: Call office of Environmental Services for assistance.**

7. Erosion Control Blanket	3885	Visual Inspection	None.	Random - See Remarks	1 m <sup>2</sup> (1 SqYd)
----------------------------	------	-------------------	-------	----------------------	------------------------------

**REMARKS: Periodic tests from approved sources to verify quality.**

8. Erosion Control Netting	3883	Visual Inspection	None.	Random - See Remarks	1 m <sup>2</sup> (1 SqYd)
----------------------------	------	-------------------	-------	----------------------	------------------------------

**REMARKS: Periodic tests from approved sources to verify quality.**

9. Peat Moss	3880	Final Inspection at Job Site	None.	For material furnished in bulk; one sample for 100 m <sup>3</sup> (100 Cu Yd) or less. An additional sample for each 200 m <sup>3</sup> or less thereafter.	2-1/4 kg (5 lb.)
--------------	------	------------------------------	-------	---	---------------------

**REMARKS: SUBMIT SAMPLES IN MOISTURE PROOF BAGS.**

**Materials furnished in packaged form may be accepted on the basis of guaranteed analysis.**

10. Sod	3878	Final Visual Inspection at site. No form 2415 required.	None.		
---------	------	---	-------	--	--

11. Silt Fence	3886	Visual Inspection Check Product Label	None.	Random - See Remarks	1 m (1 Yd)
----------------	------	--	-------	----------------------	---------------

**REMARKS: Accepted, based on manufacturers guaranteed results, with periodic sampling to verify quality.**

12. Flotation Silt Curtain	3887	Visual Inspection	None.	Random - See Remarks	1 m (1 Yd)
----------------------------	------	-------------------	-------	----------------------	---------------

**REMARKS: Accepted, based on manufacturers guaranteed results, with periodic sampling to verify quality.**

13. Compost	3890	Visual Inspection Form 2415 or Form 2403 <u>is required</u>	2415 or 2403		12 kg (25 lb.)
-------------	------	---	--------------------	--	-------------------

A. Certified Source				Random - See Remarks	
---------------------	--	--	--	----------------------	--

**REMARKS: Accepted on the basis of certified test reports furnished to the Engineer by the supplier. Periodic sampling to verify quality.**

B. Non-Certified Source				<b>MUST BE SAMPLED -</b> One Sample per 300 m <sup>3</sup> (500 Cu Yd)	
-------------------------	--	--	--	---	--

**REMARKS: Submit samples six weeks before use. Small quantity 75 m<sup>3</sup> (100 CuYd) or less.**

**SCHEDULE OF MATERIALS CONTROL**

**VI. AGRICULTURAL ITEMS (Cont'd)**

Kind of Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate Laboratory Testing	Sample Size
<b>14. Erosion Stabilization Blanket</b>	3888	Visual Inspection	None	Random - See Remarks	1 m <sup>2</sup> (1 SqYd)

**REMARKS: Periodic tests from approved sources to verify quality.**  
 \*\*\*\*\*

<b>15. Sediment Mat</b>	3894	Visual Inspection	None	Random - See Remarks	1 m <sup>2</sup> (1 SqYd)
-------------------------	------	-------------------	------	----------------------	---------------------------

**REMARKS: Periodic tests from approved sources to verify quality.**  
 \*\*\*\*\*

<b>16. Fiber Log</b>	3895	Visual Inspection	None	Random - See Remarks	1 m (1 Yd)
----------------------	------	-------------------	------	----------------------	------------

**REMARKS: Periodic Tests from approved sources to verify quality.**  
 \*\*\*\*\*

**SCHEDULE OF MATERIALS CONTROL**

**VII. CHEMICAL ITEMS**

Material	Minimum Required Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Sampling Rate for Laboratory Testing	Sample Size
1. Asphalt Plank	3204	Visual Inspection		1 sample per 1,000 plank or less of each thickness in each shipment	3 PCS 1 m long (1 Yd) each from different plank

**REMARKS: Will bear "Inspected" tag when tested and inspected prior to shipment.  
CALL BITUMINOUS LABORATORY (651) 779-5548**

2. Calcium Chloride	3911			Liquid: 1 per 40,000 L (1 per 10,000 gal) Dry: 1 per shipment	0.5 L (1 pint) 0.5 kg (1 lb.) in Plastic Container
---------------------	------	--	--	--	--

3. Water Proofing Materials Visual Inspection

A. Asphalt Primer	3165			1 sample from each shipment of each material	0.5 L (1 pint)
Waterproofing Asphalt	3166				

**REMARKS: Containers will be stamped if approved prior to shipment.  
CALL BITUMINOUS LABORATORY (651) 779-5548**

B. Fabric	3201			1 per shipment	1 m <sup>2</sup> (1 SqYd)
C. Membrane	2481			1 per shipment (Membrane Only)	0.1 m <sup>2</sup> (1 SqFt)

4. Paints	3500	Visual Inspection	2415 or 2403	1 per batch not marked approved. For pre-approved paints submit form 2415 listing batch number.	0.5 L (1 pint)
A. Non-Striping Paints	Series				

**REMARKS: Usually inspected and stamped at source. See Special Provisions For Approved Products List.  
Call Laboratory at (651) 779-5550**

B. Traffic Marking Paints	Special Provisions			None unless Suspect material	0.5 L (1 pint)
---------------------------	--------------------	--	--	------------------------------	----------------

**REMARKS: Approved Manufacturers Only. See Special Provisions For Approved Manufacturers List. Usually sampled at source and pretested.  
Call Laboratory at (651) 779-5550**

C. Epoxy Paints (Traffic Marking)	Special Provisions			None unless Suspect Material	0.5 L (1 pint) each Component
-----------------------------------	--------------------	--	--	------------------------------	-------------------------------

**REMARKS: Approved Manufacturers Only. See Special Provisions For Approved Manufacturers List. Usually sampled at source and pretested.  
Call Laboratory at (651) 779-5550.**

5. Glass Beads (Drop On)	Special Provisions			None unless Material suspect	One L (1 qt)
--------------------------	--------------------	--	--	------------------------------	--------------

**REMARKS: Approved Manufacturers Only. See Special Provisions For Approved Manufacturers List. Usually sampled at source and pretested.  
Call Laboratory at (651) 779-5548.**

6. ReflectORIZED Marking Tape	3353 3354 3355			1 clean sample of each color	1 m (1 yd)
-------------------------------	----------------------	--	--	------------------------------	------------

7. Sign and Markers	3352	Visual Inspection	2415 or 2403		
---------------------	------	-------------------	--------------------	--	--

**REMARKS: Manufacturer's stock is usually pretested by the laboratory.  
CALL ANALYTICAL CHEMICAL LABORATORY (651) 779-5550**

**SCHEDULE OF MATERIALS CONTROL**

**VIII. METALLIC MATERIALS AND METAL PRODUCTS**

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>1. Guard Rail</b>					
A. Fittings - Splicers, Bolts, etc.	3381	Visual Inspection	2415 or 2403 for small quantity	Bolts: 2 Post bolts and 4 splice bolts with nuts for each 1,000 units or less.	
B. Cable	3381	Visual Inspection	Same	1 sample from each spool	1.2 m (4 ft)
C. Structural Plate Beam	3382	Visual Inspection	Same	One .025x.25 m (1inx10in) from one edge of one of each 200 RAIL SECTIONS or One of each 100 TERMINAL SECTIONS	

**REMARKS:**

To be approved before use.

Pre-tested or Inspected will carry "Inspected" tag.

Not Pre-tested:

Submit laboratory samples at required laboratory rate.

For small quantities, lab samples not required, but document on Form 2415 or 2403 and maintain in project file.

**SMALL QUANTITIES:**

- Rail Sections - 20 or less
- Terminals - 10 or less
- Post Bolts - 100 or less
- Splice Bolts - 100 or less

**2. Steel Posts**

A. Sign Posts	3401	Visual Inspection	2415 or 2403 for small quantity	Two posts per shipment of each MASS per UNIT LENGTH	Submit shortest length of each weight
B. Fence Posts, Top Rails and others	3403* 3406* 3379 3408	Visual Inspection	Same	One sample per 500 pieces or less, but not less than two samples per shipment. Cut 0.3 m (1 ft) from each end of pipe. One each of fittings or hardware items.	

**REMARKS:**

\* For 3403, submit certified mill analysis with sample.

\* For 3406, submit Certificate of Compliance and certified mill analysis with sample.

**SCHEDULE OF MATERIALS CONTROL**

**VIII. METALLIC MATERIALS AND METAL PRODUCTS (Cont'd)**

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>3. Fence Wire</b>					
A. Barbed	3376	Visual Inspection	2415 or 2403	One sample per 50 spools or fraction thereof	1 m (3 ft)
B. Woven	3376	Visual Inspection	Same	One full height sample per 50 rolls	1 m (3 ft)
C. Chain Link Fabric	3376	Visual Inspection	Same	One sample for each 1,500 m (5,000 ft) of fencing.	0.3 m (1 ft)
<b>4. Water Pipe and other Piping Materials</b>					
	3364, 3365, 3366 & Special Provisions		2415 or 2403		

**REMARKS: To be identified and tested if necessary prior to use. Retain Form 2415 or 2403 in project files. SEE SPECIAL PROVISIONS.**

<b>5. Reinforcing Steel</b>					
A. Bars					
1. Uncoated	3301	Visual Check for Size and Grade Marking	2415 or 2403	NO FIELD SAMPLE NECESSARY	
2. Epoxy Coated		Visual Check for Size and Grade Marking and "Inspected" tag (See Remarks)	Same	One sample (1 bar) of each size bar for each day's coating production	1 m (3 ft)

**REMARKS: For Uncoated bars - Retain Certificate of Compliance and Certified Mill Analysis in Project File. For Epoxy Coated bars - Shipping paperwork will include Mn/DOT Lab #'s or steel will be tagged "Inspected" when it has been sampled and tested prior to shipment. Will be tagged "Sampled" when testing has not been completed prior to shipment. Submit samples and Certificate of Compliance if not tagged "Sampled" or "Inspected".**

B. Steel Fabric	3303	Visual Inspection		NO FIELD SAMPLE NECESSARY	
-----------------	------	-------------------	--	---------------------------	--

**REMARKS: Retain Certificate of Compliance in project file.**

C. Dowel Bars	3302			One Dowel Bar from each shipment	Full Size Dowel Bars
---------------	------	--	--	----------------------------------	----------------------

**REMARKS: Same as Epoxy Coated Reinforcing Steel**

D. Prestressing Strand	3348			One sample (2 strands) from each heat	1.5 m (5 ft)
------------------------	------	--	--	---------------------------------------	--------------

**REMARKS: Submit one copy of mill certificate and one copy of the stress-strain curve representative of the lot with the samples.**

E. Spirals	3305			One per shipment	0.6 m (2 ft)
------------	------	--	--	------------------	--------------

**REMARKS: Will be tagged with "Inspected" tag when tested prior to shipment.**

\*\*\*\*\*

<b>6. Drainage Castings</b>					
	3321	Visual Inspection*	2415 or 2403	ALL CASTINGS	
	2471			Two tensile bars to be cast with each heat at Foundry and submitted to the Laboratory BY AN APPROVED FOUNDRY*	

\* Call Maplewood Laboratory at 651-779-5540 for list of approved foundries

**REMARKS: Inspect in the field and retain Form 2415 or 2403 in project file, showing NAME OF FOUNDRY AND QUANTITY**

**SCHEDULE OF MATERIALS CONTROL**

**IX. MISCELLANEOUS MATERIALS**

Material	Spec. No.	Minimum Required Acceptance Testing Field Testing Rate	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
*****					
1. Timber, Lumber Piling and Posts	3412 to 3471 and 3491	Visual Inspection	2415 or 2403		

**REMARKS:**

Untreated materials shall be inspected in the field and the results reported on Form 2415 or 2403.

Treated materials shall be Certified on the Invoice or Shipping Ticket.

Material is inspected and stamped by an Independent Agency as per Specification 3491. Contact Laboratory for additional information.

*****					
2. Miscellaneous pieces and Hardware (Galvanized)	3392 3394		2515 or 2403	One sample of each item per shipment. Sample critical items only. (CRITICAL ITEMS ARE LOAD BEARING, STRUCTURALLY NECESSARY ITEMS.)	

**REMARKS:**

Will carry "Inspected" tag if sampled and tested prior to shipment. No sample necessary if "Inspected".

*****					
3. Insulation Board	3760	Visual Inspection	2415 or 2403	None	
*****					
4. Elastomeric Bearing Pads	3741 and Special Provisions	Check dimensions Check repair of tested pad		One sample of each size pad if not previously tested.	Full size pad

**REMARKS:**

Submit copy of Certificate of Compliance with pad.

**DO NOT USE ANY PADS THAT ARE NOT CERTIFIED**

\*\*\*\*\*



**SCHEDULE OF MATERIALS CONTROL**

**X. PIPE, TILE, AND PRECAST/PRESTRESSED CONCRETE STRUCTURES**

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
<b>1. Corrugated Metal Products</b>					
A. Culvert Pipe	3225 thru	Visual Inspection:	2415 or		
Underdrains	3229,	Check for good	2403		
Erosion control Structures	3351, and 3399	construction, workmanship, finish requirements and shipping			
<b>REMARKS:</b> Make certain pipe is Certified on Invoice					
B. Structural Plate	3231	Visual Inspection: Invoice shall include notation that material described is in accordance with fabricator's Certificate and Guarantee	2415 or 2403		
C. Aluminum Structural Plate	3233				
<b>REMARKS:</b> The Fabricator's Certificate and Guarantee shall be on file in the Mn/DOT Central Laboratory.					
*****					
<b>2. Clay Pipe</b>	3251	No samples required for less than 100 pieces	2415 or 2403	1 sample per 200 pieces of each size.	Full Size Pipe
<b>REMARKS:</b> To be sampled and inspected in the field.					
*****					
<b>3. Concrete Pipe</b>	3236	Field Inspection: Check for damage and defects	2415 or 2403		
A. Reinforced Pipe and Arches		Check dimensions as required.			
Precast Cattle Pass Units					
Sectional Manhole Units					
B. Non-Reinforced Concrete Pipe	3253			2 samples of each size from each source unless inspected and stamped at source.	Full Size Pipe
<b>REMARKS:</b> Pipe will be certified or inspected, tested and stamped at source. Only spot checks for dimensions are performed. Make certain pipe with certified mark is certified on invoice.					
*****					
<b>4. Precast/Prestressed Concrete Structures</b>					
A. Reinforced Precast Box Culvert	3238	<u>Tests by Producers</u> 1 Air test per day (1st load) 2 cylinders per pour for positive slump concrete. (1 for records, 1 for shipping)	2415 or 2403	<u>Tests by Mn/DOT</u>	
B. Precast/Prestressed Concrete Structures (beams, posts, etc.)	2405				
	3126 (Fine Aggregate)	Gradation: 1 per 150 m <sup>3</sup> (200 CuYd) or fraction thereof. 1 per day of production or 3 per week, whichever is less.	2449 2153	Gradation: 1 per month per plant Quality (Litho): 1 per month per plant	10 kg (25 lb.)
	3137 (Coarse Aggregate)	Gradation: 1 per 75 m <sup>3</sup> (100 CuYd) or 115 metric Ton (125 Ton) or fraction thereof. 1 per day of production or 3 per week, whichever is less.		Gradation: 1 per month per plant Quality (Litho): 1 per month per plant	10 kg (25 lb.)
<b>REMARKS:</b> Precast/prestressed structures including boxes will be inspected and stamped at source. Only spot checks for dimensions are performed.					

**SCHEDULE OF MATERIALS CONTROL**

**X. PIPE, TILE, AND PRECAST/PRESTRESSED CONCRETE STRUCTURES (Cont'd)**

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
5. Manholes and Catch Basins (Construction)	2506 3622	Field Inspection: Check for damage and defects. Check dimensions as required.	2415 or 2403		

**REMARKS:**

Maintain Form 2415 or 2403 in project records, showing source of materials and type and quantity of materials used. (Bricks, blocks precast or combination)

6. Drain Tile (Clay or Concrete)	3276	Visual Inspection		2 samples of each size from each source	
7. Thermoplastic (TP) Pipe ABS and PVC	3245	Obtain Certificate of Compliance. Check for approved marking printed on pipe. Field Inspect for damage or defects.	2415 or 2403		

**REMARKS:**

See Spec. 2345 for specific AASHTO or ASTM Pipe types are approved under this specification. If perforated, holes should be 5mm - 10 mm (3/16 - 3/8 inch) diameter, two rows for 4", and four rows for 6" diameter; approximately 75 mm (3 inches) on center.

8. Corrugated Polyethylene Pipe - PVC and ABS	3278	Check for markings (AASHTO M 252) Certificate of Compliance Field Inspect for damage or defects..	2415 or 2403	No Laboratory tests required	
9. Sewer Joint Sealing Compound	3724			One per shipment	0.5 L (1 pt.)
10. Preformed Plastic Sealer for Pipe	3726 Type b			One from each source	0.3 m (1 ft)
11. Bituminous Mastic Joint Sealer for Pipe	3728	Visual Inspection		Sample, if questionable	
12. Geotextile Fabric	3733 and Special Provisions	Visual Inspection for damage and uniformity of texture. Rolls of both geotextile and geotextile wrapped PE Tubing must be wrapped in UV protective plastic. (Usually Black)		(a) 1/15,000 m (50,000 LF) or fraction thereof for pipe wrap or trench lining for Permeable base designs. (b) 1/10 rolls or fraction thereof of each type fabric for all other uses. (c) Sewn seam, if required, 1/project minimum, additional as appropriate	(a) 3m (10 LF) (b) 3m <sup>2</sup> (4SqYd)* (c) 3m (10 LF)

**REMARKS:**

Submit Certificate of Compliance with fabric identification (Tyvar 3341, Supac 8NP, Mirafi 500X, etc.) and roll number. Contact Geology Unit for small quantity testing and questions. See Tech Memo 98-13-MRR-05, dated May 7, 1998.

\* Do not sample first 1 m (3 ft) of rolled Geotextile. Cut 1 m (3ft) wide strip across width of roll [Usually 3 - 4 m (12 - 14 ft)]

**SCHEDULE OF MATERIALS CONTROL**

**XI. BRICK, STONE, AND MASONRY UNITS**

<b>Material</b>	<b>Spec. No.</b>	<b>Minimum Required Acceptance Testing (Field Testing Rate)</b>	<b>Form No.</b>	<b>Minimum Required Sampling Rate for Laboratory Testing</b>	<b>Sample Size</b>
-----------------	------------------	---	-----------------	--	--------------------

**1. Brick**

A. Sewer and Masonry	3612 to 3615	Visual Inspection		One sample per 50,000 brick or fraction thereof	5 whole brick
B. Concrete Sewer*	3616	Visual Inspection		One sample per 50,000 brick or fraction thereof	5 whole brick

**Air entrainment required. Obtain air content statement from supplier.**

**2. Concrete Masonry Units**

A. For Sewer Construction	3621	Visual Inspection		One sample per shipment	5 whole units
---------------------------	------	-------------------	--	-------------------------	---------------

**Air entrainment required. Obtain air content statement from supplier.**

B. For Modular Block Retaining Walls	Special Provisions	Visual Inspection		One sample per shipment	6 whole units
--------------------------------------	--------------------	-------------------	--	-------------------------	---------------

<b>3. Reinforced Concrete Cribbing</b>	3661	Concrete control tests Air Tests Visual Inspection if previously tested	2415 or 2403	One cylinder per 100 units, but not less than 5 cylinders for a given contract. Other materials as required herein.	150x300 mm (6 x 12 in) Cylinders
--	------	---	--------------	---	--

**REMARKS:**

**Will be stamped when inspected prior to shipment.**

<b>4. Stone for Masonry or Rip-Rap</b>	3601 and Special Provisions	Visual Inspection Submit Form 2415 unless special testing is specified	2415 or 2403		
--	-----------------------------	---	--------------	--	--

**REMARKS:**

**Each source shall be approved by Project Engineer or Supervisor for quality prior to use.**

**For questions on quality, contact District Materials or Geology Unit**

**SCHEDULE OF MATERIALS CONTROL**

**XII. ELECTRICAL AND SIGNAL EQUIPMENT ITEMS**

Material	Spec. No.	Minimum Required Acceptance Testing (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
*****					
1. Lighting Standards (Aluminum or Steel)	3811	Visual Inspection			
<b>REMARKS:</b>					
The Fabricator will submit "Certificate of Compliance", on a per project basis, to the Structural Metals Engineer.					
*****					
2. Hand Holes and Pull Boxes (Precast) (PVC)	2545		2415 or		
	2550		2403		
	2565				
<b>REMARKS:</b>					
Will be inspected at source by laboratory upon notification. For cast iron frame and cover: see VIII.6, Drainage Castings					
*****					
3. Foundation	2545	Slump as needed		1 cylinder per 20 m <sup>3</sup> (25 CuYd)	
*****					
4. Conduit and Fittings					
	3801				
A. Metallic	3802	Visual Inspection	2415 or	None	
	3803		2403		
<b>REMARKS:</b>					
Conduit will bear UL labels					
-----					
B. Non-Metallic		Visual Inspection	2415 or	Submit samples if not approved by brand	
			2403		
<b>REMARKS:</b>					
Retain Form 2415 or 2403 in Project File					
*****					
5. Anchor bolts	3811.2B(5)	Visual Inspection		1 per 100 Units (per Type per Lot Number per Project)	
<b>REMARKS:</b>					
The Fabricator will submit test specimens (in quantities sufficient to meet the noted test frequency) to the Maplewood Lab. A copy of the test report will be forwarded to the Structural Metals Engineer.					
*****					
6. Miscellaneous Hardware		Visual Inspection		Sample critical items only. One of each item per shipment. (Critical Items are load bearing, structurally necessary items.)	
<b>REMARKS:</b>					
Will carry "Inspected tag if sampled and tested prior to shipment. No sample necessary if "Inspected". Do Not use if not tested. Field sample at sampling rate for laboratory testing.					
*****					
7. Cable and Conductors					
A. Single Electrical Conductors (No Jacket)	3815.2B1	Visual Inspection	2415 or	None	
	3815.2B2(a)		2403		
<b>REMARKS:</b>					
Make certain the conductors are the type specified. Submit Field Inspection report showing type and quantities used. Shall bear UL label and type where applicable.					
-----					
B. Electrical Cables and Single Conductors with Jacket	3815.2B2(b)	Visual Inspection	2415 or	1 sample per size per lot	1 m (1 Yd)
	3815.2B3		2403		
	3815.2B4				
	3815.2C1				
	3815.2C3				
	3815.2C4				
	3815.2C5				
	3815.2C6				
	3815.2C7				
	3815.2C8				
C. Fiber Optic Cables	3815.2C13	Visual Inspection	2415 or	1 sample per size per lot	1 m (1 Yd)
			2403		
<b>REMARKS:</b>					
Usually inspected (B&C) at source and spools stamped. If spools are not stamped, submit sample and material certification from manufacturer.					

SCHEDULE OF MATERIALS CONTROL

XII. ELECTRICAL AND SIGNAL EQUIPMENT ITEMS (Cont'd)

Materials	Spec. No.	Minimum Required Acceptance Tasting (Field Testing Rate)	Form No.	Minimum Required Sampling Rate for Laboratory Testing	Sample Size
8. Ground Rods	2545	Visual Inspection	2415 or 2403	None.	

REMARKS:

Retain Form 2415 or 2403 in project file.

9. Luminaires and Lamps	2545	2403	2415 or		
-------------------------	------	------	---------	--	--

REMARKS:

Approved by Brand Name.

The conductors shall bear UL label and type, where applicable.

10. Electrical Systems.

To be reported as a "System" using the LIGHTING, SIGNAL AND TRAFFIC RECORDER INSPECTION REPORT

To be certified by the Project Engineer

11. Traffic Signal Systems.

To be reported as a "System" using the LIGHTING, SIGNAL AND TRAFFIC RECORDER INSPECTION REPORT

To be certified by the Project Engineer